



0480




CTOVU 0480

CTOVU 0480



Date: 12 March 2025

SLF TEST REPORT

1	Customer's Name	M/s JBM AUTO LTD.
2	Customer's Address	Plant 1 : JBM AUTO LTD, HSIIDC, INDUSTRIAL ESTATE, PLOT NO. 118, SECTOR 59, BALLABGARH, FARIDABAD - 121 004 (HARYANA) Plant 2 : JBM AUTO LTD, PLOT NO A-04, INDUSTRIAL AREA, KOTWAN, KOSI KALAN, MATHURA, UTTAR PRADESH-281 403 Plant 3 : JBM ELECTRIC VEHICLES PRIVATE LIMITED, 81 KM MILESTONE , DELHI AGRA HIGHWAY NH2, VILLAGE BANCHARI, TEHSIL – HODEL, DISTRICT PALWAL, HARYANA, 121 106
3	Description of test sample	Speed Limitation Function is an integral part of MCU.
4	Test Objective	To carry out the performance test on the Speed Limitation Function (SLF), as installed on vehicle as per CI. No. 5.7.3 of AIS-018 : 2001, upto Amendment No. 5, 2017 for the tested vehicle model - "ECOLIFE E9 LF" at 40, 60 km/h
5	Conclusion	Refer Test Results on page 2
5.1	The Speed Limitation Function (SLF), specified in Sr. No. 3 of this test report with set speed of 40, 60 km/h meets the specified requirements of CI. No. 5.7.3 of AIS-018/2001, when installed on vehicle model: ECOLIFE E9 LF, M3 category of vehicle.	
For more details of vehicle refer page no. 4 of 7 of this report.		
CAUTION: TO BE OBSERVED BY THE TRANSPORT AUTHORITY		
<div><p>The tamper proofness of the SLF installation has been ensured, on the vehicle submitted for type approval. However the Transport Authorities are requested to verify the MCU/VCU ID as shown in installation photographs of this report. Since SLF is an OEM controlled activity, the onus of compliances are the responsibility of the OEM</p></div>		
Remarks	1. Place of Issue : ICAT Centre II	
ICAT Reference		CVTEJBMAUCCSC185001
		Please turn over for DISCLAIMER
<div><p>0480te:12March2025M/sJBMAUTOLTD,HSIIDC,INDUSTRIAL</p></div>		<div><p>0480te:12March2025M/sJBMAUTOLTD,HSIIDC,INDUSTRIAL</p></div>
Manish Kumar Manager	Keshav Kr. Tripathi Asst. General Manager	Saurabh Dalela Director
		Page 1 of 7