C	T	0	V	T	0652

CTOVT0652

Date:	23-04-2024

SLF REPORT

1	Customer's Name	**M/s SHIGAN TELEMATICS PRIVATE LIMITED**
2	Customer's Address	**Khasra No. 41/24, 48/4, Nagali, Khera Kalan Road, Opposite OM Dharam Kanta, Khera Garhi, Delhi-110042**
3	Description of test sample	**Speed Limitation Function is an integral part of ECU.**
4	Test Objective	**To carry out the performance test on the Speed Limitation Device (SLD), as installed on vehicle as per Cl. No. 5.7.3 of AIS-018 2001, upto Amendment No. 5, 2017.**
5	Conclusion	**Refer Test Results on page 2.**
5.1	The Speed Limitation Function (SLF), specified in Sr. No. 3 of this test report with set speed of **40, 60, 80 km/h** meets the specified requirements of Cl. No. 5.7.3 of AIS-018/2001, when installed on vehicle model: **TATA LPT 2515 TC** , N3 category of vehicle.	

For more details of vehicle refer page no. 4 of 7 of this report.

CAUTION: TO BE OBSERVED BY THE TRANSPORT AUTHORITY

CAUTION

The tamper proofness of the SLF installation has been ensured, on the vehicle submitted for type approval. However the Transport Authorities are requested to verify the ECU ID as shown in installation photographs of this report. Since SLF is an LNG retrofitter controlled activity in this case, the onus of compliances are the responsibility of the LNG retrofitter .

Remarks	1. Place of Issue : ICAT Centre II

ICAT Reference	CCTNSGNTTDVEL175677	Please turn over for DISCLAIMER

0652Date:23-04-2024M/sSHIGANTELEMATICSPRIVATELIMITEDKhasraNo.41/24,48/4,

0652Date:23-04-2024M/sSHIGANTELEMATICSPRIVATELIMITEDKhasraNo.41/24

0652Date:23-04-2024M/sSHIGANTELEMATICSPRIVATELIMITEDKhasraNo.41/24,48/4,Na

Gavendra Singh Manager	Keshav Kr. Tripathi Asst. General Manager		SAURABH DALELA DIRECTOR	Page 1 of 7