



|   |   |   |   |   |      |
|---|---|---|---|---|------|
| C | T | O | P | R | 0731 |
|---|---|---|---|---|------|

Date : 14<sup>th</sup> June 2022

|         |                    |
|---------|--------------------|
| ULR NO. | TC536022150000550F |
|---------|--------------------|

|                                    |             |  |                      |                       |                   |  |  |
|------------------------------------|-------------|--|----------------------|-----------------------|-------------------|--|--|
| <b>Battery Nominal Voltage (V)</b> |             | 60   |                      |                       |                   |  |  |
| <b>Traction Motor</b>              | <b>Make</b> | M/s Sai Kirish Energy Company  |                      |                       |                   |  |  |
|                                    | <b>ID</b>   | SKM60V250  | <b>Max Power(kW)</b> | 0.180                 |                   |  |  |
| <b>Power Controller</b>            | <b>Make</b> | M/s Sai Kirish Energy Company  |                      |                       |                   |  |  |
|                                    | <b>ID</b>   | SKC60V250  | <b>Rating</b>        | 60V / 5A              |                   |  |  |
| <b>Test Date</b>                   |             | 13 <sup>th</sup> June 2022   |                      |                       |                   |  |  |
| <b>Test Results</b>                |             |  |                      |                       |                   |  |  |
| <b>Test Procedure</b>              |             | <b>Type of Test</b>  |                      | <b>Measured Value</b> |                   |  |  |
| <b>AIS-041:2003</b>                |             | <b>Vehicle maximum 30 minute speed</b>   |                      | 22.1 km/h             |                   |  |  |
|                                    |             | <b>Vehicle maximum 30 minute power</b>   |                      | 0.166 kW at 15.5 km/h |                   |  |  |
|                                    |             | <b>Vehicle net power</b>   |                      | <b>Speed (km/h)</b>   | <b>Power (kW)</b> |  |  |
|                                    |             |  |                      | 20                    | 0.136             |  |  |
|                                    |             |  |                      | 16                    | 0.163             |  |  |
|                                    |             |  |                      | 12                    | 0.176             |  |  |
|                                    |             |  |                      | 10                    | 0.180             |  |  |
|                                    |             |  |                      | 8                     | 0.174             |  |  |
|                                    |             |  |                      | 6                     | 0.146             |  |  |
| <b>Remarks:-</b>                   |             | 1. The tests were conducted as per the requirements of AIS-041:2003.   |                      |                       |                   |  |  |
|                                    |             | 2. Tests were conducted by powering the vehicle using external power supply after disconnecting the vehicle battery. |                      |                       |                   |  |  |
|                                    |             | 3. Tests were conducted at ICAT Centre-1, Manesar.   |                      |                       |                   |  |  |

|   |  |   |  |
|---|--|---|--|
| <b>AUTHORISED SIGNATORY</b>   |  |   |  |
| <b>Prepared By</b>  |  | <b>Checked By</b>   |  |
| SHUBHAM GAGAL<br>Engineer   |  | MONAL HASTI<br>Manager  |  |
|  |  |  |  |
|   |  | Page 2 of 2   |  |