



C O S S 0870

Date : 29th September 2023

ANNEXURE - I

| Sr. No. | Trailer Nomenclature | Overall Length (mm) | Wheel-base (mm) | Suspension Type* & GCW (kg) | Unladen weight of trailer (kg) | ABS System make & configuration |
|---------|---------------------------|---------------------|-----------------|-----------------------------|--------------------------------|---------------------------------|
| 12 | NT-TA 32FT IA SW TR-660 | 9,760 | 6,600 | MMM - 53,000 | 8,000 | M/s. Wabco India, 4S3M |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 13 | NT-TA 32FT IA SW TR-1295 | 9,760 | 5,820 | MMM - 53,000 | 8,000 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 14 | NT-TA 32FT IA SKL TR-660 | 9,760 | 6,600 | MMM - 53,000 | 7,070 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 15 | NT-TA 32FT IA SKL TR-1295 | 9,760 | 5,560 | MMM - 53,000 | 7,070 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 16 | NT-TA 40FT IA FB TR-885A | 12,200 | 8,185 | MMM - 53,000 | 9,250 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 17 | NT-TA 40FT IA FB TR-756A | 12,298 | 8,289 | MMM - 53,000 | 9,315 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 18 | NT-TA 40FT IA FB TR-756 | 12,298 | 7,942 | MMM - 53,000 | 9,315 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 19 | NT-TA 40FT IA FB TR-1370 | 12,298 | 8,428 | MMM - 53,000 | 9,315 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 20 | NT-TA 40FT IA SW TR-756 | 12,298 | 7,942 | MMM - 53,000 | 10,000 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |
| 21 | NT-TA 40FT IA SKL TR-756 | 12,298 | 7,942 | MMM - 53,000 | 8,835 | |
| | | | | AMM - 54,000 | | |
| | | | | AAA - 55,000 | | |

*A-Air/Pneumatic, M-Mechanical, 1 tonne extra load is permitted for each axle fitted with pneumatic suspension as per S.O. 3467(E) dt.16th July, 2018 with S.O. 3881(E) dt. 06th August, 2018.
 55 tonne GCW issued with AAA - 3 Independent pneumatic suspended axles and maximum per axle safe weight is 12.17 tonne,
AMM - Single pneumatic suspended axle + two independent mechanical suspended axle,
MMM - Three Independent mechanical suspended axles

AUTHORISED SIGNATORY

VIKAS SADAN
DEPUTY GENERAL MANAGER



Saurabh Dalela

SAURABH DALELA
DIRECTOR

