


C	T	0	V	T	1499
---	---	---	---	---	------

CT0VT 1499

Date: 20 September 2024

SLF TEST REPORT

1	Customer's Name	M/s JBM AUTO LTD.		
2	Customer's Address	Plant 1 : JBM AUTO LTD, HSIIDC, INDUSTRIAL ESTATE, PLOT NO. 118, SECTOR 59, BALLABGARH, FARIDABAD - 121 004 (HARYANA) Plant 2 : JBM AUTO LTD, PLOT NO A-04, INDUSTRIAL AREA, KOTWAN, KOSI KALAN, MATHURA, UTTAR PRADESH-281 403 Plant 3 : JBM ELECTRIC VEHICLES PRIVATE LIMITED, 81 KM MILESTONE , DELHI AGRA HIGHWAY NH2, VILLAGE BANCHARI, TEHSIL – HODEL, DISTRICT PALWAL, HARYANA, 121 106		
3	Description of test sample	Speed Limitation Function is an integral part of MCU.		
4	Test Objective	To carry out the performance test on the Speed Limitation Function (SLF), as installed on vehicle as per Cl. No. 5.7.3 of AIS-018 : 2001, upto Amendment No. 5, 2017 for the tested vehicle model - ECOLIFE E12 GALAXY at 40 km/h & 60 km/h		
5	Conclusion	Refer Test Results on page 2.		
5.1	The Speed Limitation Function (SLF), specified in Sr. No. 3 of this test report with set speed of 40 km/h & 60 km/h meets the specified requirements of Cl. No. 5.7.3 of AIS-018/2001, when installed on vehicle model: "ECOLIFE E12 GALAXY", M3 category of vehicle.			
For more details of vehicle refer page no. 4 of 7 of this report.				
CAUTION: TO BE OBSERVED BY THE TRANSPORT AUTHORITY				
		The tamper proofness of the SLF installation has been ensured, on the vehicle submitted for type approval. However the Transport Authorities are requested to verify the ECU ID as shown in installation photographs of this report. Since SLF is an OEM controlled activity, the onus of compliances are the responsibility of the OEM .		
Remarks	1. Place of Issue : ICAT Centre II			
ICAT Reference		CVTNJBMATBCSC174157		Please turn over for DISCLAIMER
Karan Mahajan Dy. Manager		Keshav Kr. Tripathi Asst. General Manager		SAURABH DALELA DIRECTOR
				Page 1 of 7